



TREES WITHOUT VISIBLE ROOT FLARE SHALL BE REJECTED BEFORE PLANTING. PLACE ROOT FLARE LEVEL OR 1" ABOVE FINISH GRADE. DO NOT COVER TOOR FLARE WITH SOIL OR MULCH. TURF OR GROUNDCOVER PER PLANS - REMOVE WIRE AND BURLAP TO BOTTOM OF ROOT BALL AFTER SETTING IN PIT - PLACE ROOT BALL ON UNDISTURBED SOIL TO REDUCE SETTLING - ROOT BARRIER, BOTH SIDES TAMP SOIL AROUND ROOT BALL FIRMLY W/ FOOT PRESSURE SO THAT THE ROOT BALL DOES NOT

NOTE: FOR GUYING AND STAKING, SEE DETAIL THIS SHEET.

TREE IN PLANTING STRIP 32 9343.33-02

1/2" DIA. BLACK PLASTIC HOSE GALVANIZED WIRE OR CABLE, 14-GAUGE FOR 2.5IN CALIPER OR LESS. 12-GAUGE FOR TREES MORE THAN 2.5IN CALIPER. TWIST WIRE TO TIGHTEN. - 1.5IN. X 1.5IN. HARDWOOD STAKES OR OTHER APPROVED MATERIAL PAINTED BLACK. DRIVE STAKE <u>OUTSIDE</u> OF ROOTBALL. (2) STAKES PER TREE. FINISH GRADE TREE TRUNK WIND DIRECTION

1. ALIGN STAKES PERPIDICULAR OR PARALLEL TO CURB & SIDEWALK, WHICHEVER IS CLOSER TO WIND DIRECTION.

2. SEE PLANTING NOTES & SPECIFICATIONS (IF PROVIDED) FOR MORE

STREET TREE STAKING

32 9343.39-02

CONCEPT PLANT SCHEDULE

Amelanchier alnifolia `Regent` / Saskatoon Serviceberry Pyrus calleryana `Arıstocrat` TM / Arıstocrat Flowering Pear Pyrus calleryana `Chanticleer` / Chanticleer Pear



Acer freemanii `Jeffersred` TM / Autumn Blaze Maple Acer rubrum `October Glory` TM / `October Glory` Maple Fraxinus pennsylvanica `Patmore` / `Patmore` Ash Gleditsia triacanthos `Sunburst` / `Sunburst` Locust



Cornus florida / Eastern Dogwood

Malus floribunda `Prairifire` / Prairie Fire Crabapple Prunus serrulata `Kwanzan` / Flowering Cherry/Kwanzan Cherry



CRAIG

GENERAL PLANTING NOTES I. ALL PLANTING SHALL CONFORM WITH THE CITY OF LIBERTY LAKE DEVELOPMENT CODE ARTICLE 10-3C.

2. THE CONTRACTOR SHALL MAINTAIN A QUALIFIED SUPERVISOR ON THE SITE AT ALL TIMES DURING CONSTRUCTION THROUGH COMPLETION OF FINAL PUNCHLIST WORK.

3. THE CONTRACTOR SHALL VERIFY ALL PLANT MATERIAL QUANTITIES PRIOR TO INSTALLATION. ANY PLANT MATERIAL QUANTITIES LISTED ARE FOR THE CONVENIENCE OF THE CONTRACTOR. ACTUAL NUMBER OF SYMBOLS SHALL HAVE PRIORITY OVER QUANTITY DESIGNATED.

4. THE CONTRACTOR SHALL FURNISH AND PAY FOR ALL CONTAINER OR FIELD GROWN TREES, SHRUBS AND VINES, INCLUDING SEEDED AND SODDED TURF, HYDROMULCHES AND FLATTED GROUNDCOVERS. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE AND PAY FOR: PLANTING OF ALL PLANT MATERIALS; THE SPECIFIED GUARANTEE OF ALL PLANT MATERIALS; THE STAKING AND GUYING OF TREES AND THE CONTINUOUS PROTECTION OF ALL PLANT MATERIALS UPON THEIR ARRIVAL AT THE SITE.

6. GROUNDCOVER PLANTING (WHERE SPECIFIED) SHALL BE CONTINUOUS UNDER ALL TREES AND SHRUB MASSES AS SHOWN ON PLAN.

7. ALL PLANT MATERIAL SHALL BE SUBJECT TO APPROVAL BY THE LANDSCAPE ARCHITECT AND/OR OWNER PRIOR TO INSTALLATION.

8. ALL SPECIMEN TREES SHALL BE SELECTED AND SPOTTED BY THE LANDSCAPE ARCHITECT AND/OR THE OWNER'S REPRESENTATIVE PRIOR TO PLANTING.

9. ALL SOIL PREPARATION SHALL BE INSTALLED AS PER THE SOIL AGRONOMY REPORT TO BE PROVIDED AND PAID FOR BY THE LANDSCAPE CONTRACTOR. THE REPORT SHALL BE IMMEDIATELY FORWARDED TO THE LANDSCAPE ARCHITECT UPON COMPLETION.

IO. THE SOIL AMENDMENTS SPECIFIED ARE FOR BIDDING PURPOSES ONLY. THE CONTRACTOR SHALL PROVIDE FOR A SOILS AGRONOMY REPORT FROM AN APPROVED SOILS LABORATORY AND/OR ANY ADDITIONAL SPECIFICATION PROVIDED BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION OF PLANT MATERIALS.

II. REMOVE ALL STAKING AS SOON AS THE TREE HAS GROWN SUFFICIENT ROOTS AND OVERCOME THE PROBLEM THAT REQUIRED THE TREE TO BE STAKED . STAKES SHALL BE REMOVED NO LATER THE END OF THE FIRST GROWING SEASON AFTER PLANTING.

12. TREES NORMALLY DO NOT NEED TO BE STAKED AND STAKING CAN BE HARMFUL TO THE TREE. STAKING SHOULD BE DONE ONLY WITH THE APPROVAL OF THE LANDSCAPE ARCHITECT IF IT IS EXPECTED THAT THE TREE WILL NOT BE ABLE TO SUPPORT ITSELF. THE FOLLOWING ARE REASONS WHY TREES DO NOT REMAIN

* TREES WITH POOR-QUALITY ROOT BALLS OR ROOT BALLS THAT HAVE BEEN

CRACKED OR DAMAGED. REJECT RATHER THAN STAKE. * TREES THAT HAVE GROWN TOO CLOSE TOGETHER IN THE NURSERY, RESULTING IN WEAK TRUNKS. REJECT RATHER THAN STAKE. * PLANTING PROCEDURES THAT DO NOT ADEQUATELY TAMP SOILS AROUND THE ROOT

BALL. CORRECT THE PLANTING PROCEDURE. * ROOT BALLS PLACED ON SOFT SOIL. TAMP SOILS UNDER ROOT BALL PRIOR TO

* ROOT BALLS WITH VERY SANDY SOIL OR VERY WET CLAY SOIL. STAKING ADVISABLE. * TREES LOCATED IN A PLACE OF EXTREME WINDY CONDITIONS. STAKING IS ADVISABLE.

GENERAL STREET LIGHTING NOTES

I. ALL LIGHTING SHALL CONFORM WITH THE CITY OF LIBERTY LAKE DEVELOPMENT CODE ARTICLE 10-3F-2.

2. STREET LIGHTS SHALL BE SPECIFIED AND INSTALLED BY AVISTA UTILITIES. MODIFICATIONS TO THE LIGHTING PLAN SHALL BE MADE TO ENSURE PROPER FOOTCANDLE VALUES FOR ALL PORTIONS OF THE STREET. AVISTA SHALL SUPPLY A SHOP DRAWING SUBMITTAL FOR AGENCY APPROVAL PRIOR TO INSTALLING LIGHTING.

	4	
	3	
	2	
	\triangle	
	No.	DESC.
STATE OF WASHINGTON REGISTERED LANDSCAPE ARCHITECT		
CRAIG D. ANDERSEN CERTIFICATE NO. 1005	Z.	TURE

/ DATE BY

05/03/07

CDA

CDA

06-371

PROJECT

DRAWING NO.

1 OF

PLANTING

CALL BEFORE YOU DIG 456-8000